

SPRAWDZENIE ZABEZPIECZEŃ I DOBÓR WLZ

								W s p . R ó w n o m .													
Połączenia	Pinst	U	Kz	cosF	Pszcz	Qszcz	Sszcz		Iobc	Izab	Typ kabla	Długość	delta U	I dop	kabl	Rkab	War 1		War 2		
	kW	V			kW	kVAr	kVA		A	A		m	%	A		om/km	Iobc	Izab	Idop	1,6 Izab	1,45 Idop
RG-PC	44,0	400,0	1	0,94	44,0	16,0	46,8	1	67,6	100	YKY 5X35	50	0,8	112	0,524	67,6	100,0	112,0	160,0	162,4	
RG-RK	5,0	400,0	1	0,94	5,0	1,8	5,3	1	7,7	25	YKY 5X6	20	0,2	32	3,08	7,7	25,0	32,0	40,0	46,4	
RG-RPV	25,0	400,0	1	0,94	25,0	9,1	26,6	1	38,4	50	YKY 5X25	30	0,4	92	0,727	38,4	50,0	92,0	80,0	133,4	
RG-RW	5,0	400,0	1	0,94	5,0	1,8	5,3	1	7,7	20	YKY 5X6	40	0,4	32	3,08	7,7	20,0	32,0	32,0	46,4	
RG złącze	95,0	400,0	0,9	0,94	85,5	31,0	91,0	1	131,4	160	YKY 5X120	100	0,9	210	0,153	131,4	160,0	210,0	256,0	304,5	